



Project: Metal Roof Repair

3-06-2018

Attn: Jerome Krieger

Recreation Manager

City of Blaine Parks and Recreation

Jerome,

We propose the following:

Lexington Athletic Complex

- Tear off and dispose of existing standing seam roof panels and metal flashing.
- Install new ice and water underlayment and ~9,000 SQ FT of 24ga. snap lock standing seam roof panels.
- Install 100 LF of commercial gutter and associated downspouts at the south and north lower roof sections.

Town Square Park

- Tear off and dispose of existing standing seam roof panels and metal flashing.
- Install new ice and water underlayment and ~3,500 SQ FT of 24ga. snap lock standing seam roof panels.

All the above for the net sum of: Two Hundred Seventeen Thousand Dollars. \$217,000.00

- Install 100 LF of continuous snow guards along the south side of the upper roof and along the lower north roof section.

Add to the base bid: Two Thousand Two Hundred Dollars. \$2,200.00

Thank you,

Paul O'Neill
Estimator

By: _____

Name: _____

Its: Mayor

Date: _____

By: _____

Name: _____

Its: City Manager

Date: _____