

GOODMANSON CONSTRUCTION

SINCE 1971

O: 651.636.4996

F: 651.636.5211

PROPOSAL

Developing Concrete Relationships

2500 County Road B W, Suite 2A
Roseville, MN 55113
GoodmansonConstruction.com

Date: 5/27/14

Proposal Submitted To:

Brian Jasken
651-248-1048
BJasken@McGough.com

Work To Be Performed At

Blain City Hall

We hereby propose to furnish the materials and perform the labor necessary for the completion of:

Power Wash and Seal Concrete (51,135s.f.)

- Pressure wash and scrub concrete with degreaser.
- Blow-dry and prepare concrete for sealer.
- Seal concrete with TK-290 Final Seal, industrial concrete sealer.
 - ✓ Large unheated garage: 22,204s.f.
 - ✓ Fire Garage 27,000s.f.
 - ✓ Police department heated garage and sally port garage 1,931s.f.

Power Wash Only:	\$8,000.00
Power Wash with TK-290 Sealer Total:	\$15,341.00
Power Wash and Tk-290 Sealer with Siloxane Dye:	\$25,567.00

Seal totals presume project will be installed over two day.

Repair Damaged Concrete

- Prep area by chipping away all loose pieces of concrete.
- Install high psi grout in deteriorating areas.
- Trowel smooth.
- Thoroughly clean affected area.
 - ✓ Two areas at the entrance of the unheated garage. (approx. 40s.f.)

Total: \$685.00

Initial _____

