





Case File No. 17-0022 Johnstons Blaine Estates







## **GRADING. DRAINAGE & EROSION CONTROL NOTES**

PRIOR TO ANY GRADING OPERATIONS, THE CONTRACTOR SHALL PROVIDE WIMCO INLET PROTECTION (OR OTHER APPROVED EQUAL) FOR ALL STORM SEWER INLETS THAT WILL RECEIVE RUN-OFF FROM CONSTRUCTION ACTIVITIES

CONTRACTOR TO PROVIDE TOPSOIL STOCKPILES AT LOCATION DESIGNATED BY OWNER PLACE STOCKPILES AS FAR FROM DRAINAGE WAYS AS POSSIBLE. PROVIDE SLIT FENCE AT DOWNSTREAM SIDE OF STOCKPILE LOCATIONS. IF STOCKPILE IS TO BE IN-PLACE LONGER THAN 7 DAYS, PROVIDE SEED AND MULCH.

THE CONTRACTOR SHALL PROVIDE ALL SOD, SEED, MULCH AND FERTILIZER WHICH SHALL CONFORM WITH THE FOLLOWING MINDOT SPECIFICATIONS AS MODIFIED BELOW.

| ITEM  | MNDOT SPECIFICATION/NOTES 3878  |  |  |
|---|---|--|--|
| SOD   |   |  |  |
| SEED **   | 3876  |  |  |
| FOR TURF ESTABLISHMENT *  | MNDOT MIXTURE 260 (100 LBS/ACRE)  OR -  MNDOT MIXTURE 270 (120 LBS/ACRE)  |  |  |
| TEMPORARY FALL COVER<br>SPRING/SUMMER<br>1-2 YEARS COVER<br>2-5 YEARS COVER | MNDOT MIXTURE 100B (100 LBS/ACRE<br>MNDOT MIXTURE 110 (AT 100 LBS/ACR<br>MNDOT MIXTURE 150 (AT 40 LBS/ACR<br>MNDOT MIXTURE 190 (AT 60 LBS/ACR |  |  |
| MULCH   | 3882 (TYPE 1 - DISC ANCHORED)   |  |  |
| FERTILIZER  | 3881  |  |  |
| WOOD FIBER BLANKET  | 3885 (CATEGORY 2)   |  |  |

- MOW A MINIMUM OF ONCE PER 2 WEEKS
   SEEDED AREAS SHALL BE EITHER MULCHED OR COVERED BY FIBROUS BLANKETS TO PROTECT SEEDS AND LIMIT EROSION.

ALL EROSION AND SEDIMENT CONTROL MEASURES SHOWN ON THE PLANS OR IMPLEMENTED IN THE FIELD SHALL BE IN ACCORDANCE WITH THE CITY AND NPDES PHASE II PERMIT REQUIREMENTS, AND THE MPCA'S "PROTECTING WATER QUALITY IN URBAN AREAS BEST MANAGEMENT PRACTICES FOR MINNESOTA.

THE CONTRACTOR SHALL PROVIDE DESIGNATED CONCRETE TRUCK WASHOUT AREA WITH APPROPRIATE SIGNAGE. WASHOUT AREA IS TO BE A MINIMUM OF 50' FROM STORM DRAINS, DITCHES, PONDS, OR OTHER STORWANTER FEATURES. ALL LIQUID AND SOLID WASTE GENERATED BY CONCRETE WASHOUT OPERATIONS MUST BE CONTAINED IN A LEAK-PROOF CONTAINED KTACILITY OR IMPERMEABLE LINER (E.G. COMPACTED CLAY LINER, IMPERMEABLE LINER (E.G. COMPACTED CLAY LINER, IMPERMEABLE). GEO-MEMBRANE). AFTER WASTE CONCRETE IS SET, BREAK-UP AND DISPOSE

THE CONTRACTOR SHALL MAINTAIN SILT FENCE, INCLUDING THE REMOVAL OF ACCUMULATED SEDIMENT, THROUGH COMPLETION OF BUILDING CONSTRUCTION SILT FENCE TO BE REMOVED ONLY AFTER COMPLETION OF BUILDING CONSTRUCTION AND UPON ESTABLISHMENT OF VEGETATION

THE CONTRACTOR SHALL PAY SPECIAL ATTENTION TO ALL ADJACENT PROPERTY LINES AND MAKE SURE THE EROSION CONTROL PRACTICES IN-PLACE IN THOSE AREAS PREVENT MIGRATION OF SEDIMENT ONTO ADJACENT PROPERTIES.

THE CONTRACTOR SHALL PROVIDE WOOD FIBER BLANKET FOR ALL AREAS OF CONCENTRATED FLOW AND FOR ALL SLOPES 3:1 OR GREATER.

IF ANY SLOPES APPEAR TO BE FAILING, THE CONTRACTOR SHALL PROVIDE ADDITIONAL SILT FENCE, BIOROLLS AND EROSION CONTROL BLANKET AS

THE CONTRACTOR SHALL FINAL GRADE SWALE AREAS UPON STABILIZATION OF UPSTREAM AREAS

THE CONTRACTOR SHALL SOD ALL DISTURBED DRAINAGE AREAS, INCLUDING SWALES, OVERFLOWS, AROUND STORM SEWER FLARED—END SECTIONS, AND OFF-STREET CATCH BASINS.

UPON GRADING COMPLETION THE CONTRACTOR SHALL PROVIDE NATIVE TOPSOIL, SEED, AND MULCH ANCHORED WITH A STRAIGHT SET DISC WITHIN 4B HOURS OF FINAL GRADING.

EXCESS SOIL SHOULD BE TREATED LIKE OTHER EXPOSED SOIL AND STABILIZED WITHIN 72 HOURS. ANY SOIL STOCKPILES ARE TO HAVE SILT FENCE PLACED ON DOWNSTREAM SIDES AND SHALL NOT BE PLACED IN SURFACE WATERS.

ADJACENT STREETS SHALL BE KEPT CLEAN OF CONSTRUCTION MATERIALS. DIRT, AND OTHER UNDESTRABLE MATERIALS. WHEN MATERIALS OR DEBBS; HAVE WASHED/FLOWED ONTO ADJACENT STREETS, IT IS THE CONTRACTOR'S RESPONSIBILITY TO SWEEP/SCRAPE STREETS AS NECESSARY OR AS DIRECTED

GRADING, DRAINAGE & EROSION CONTROL PLAN JOHNSTONS BLAINE ESTATES

| DRAWN BY:            |           | DESIGN BY<br>R.K.A. |           |  |  |
|----------------------|-----------|---------------------|-----------|--|--|
| _                    | CHCKD BY: |                     | PROJ. NO. |  |  |
|                      | C.W.P.    |                     | 17-1686   |  |  |
| ORIC                 | NAL DA    | E:                  |           |  |  |
|                      | MAY       | 5,201               | 17        |  |  |
| _                    | _         |                     | _         |  |  |
| REVISION DESCRIPTION |           |                     |           |  |  |



JOHNSTONS BLAINE ESTATES , MINNESOTA BLANE

STEVE & CINDY JOHNSTON




ENGINEERING INC.

PHONE: (651) 361-8210 FAX. (651) 361-8701

NORTH




C3



## **GENERAL NOTES**


- 1) THE INFORMATION SHOWN ON THESE DRAWINGS CONCERNING TYPE AND LOCATION OF EXISTING UTILITIES IS NOT GUARANTEED TO BE ACCURATE OR ALL INCLUSIVE. THE CONTRACTOR IS RESPONSIBLE FOR MANICH ON SO WILLIAM OF THE WAY OF THE OWN AND THE OWN AND
- 2) CALL "811" FOR EXISTING UTILITIES LOCATIONS PRIOR TO ANY EXCAVATIONS.
- 3) INSTALLATIONS SHALL CONFORM TO THE CITY STANDARD SPECIFICATIONS AND DETAIL PLATES.
- 4) THE CONTRACTOR SHALL NOTIFY CITY PUBLIC WORKS DEPARTMENT A MINIMUM OF 24 HOURS PRIOR TO THE INTERRUPTION OF ANY SEWER OR WATER SERVICES TO EXISTING HOMES OR BUSINESSES.
- 5) STORAGE OF MATERIALS OR EQUIPMENT SHALL NOT BE ALLOWED ON PUBLIC STREETS OR WITHIN PUBLIC RIGHT-OF-WAY.
- 6) NOTIFY CITY A MINIMUM OF 48 HOURS PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.















PHONE: (451) 351-4216 -AX: (451) 361-8701



1 INC 1= 30 FEET

CIVIL SITE AND, UTILITIES PLAN JOHNSTONS BLAINE ESTATES

**G2**