## NATIONAL SPORTS CENTER ACCESS ROADWAY AND PARKING LOTS PROJECT Phase 1 Preliminary Construction Cost Estimate DATE: January 29, 2019

ltem	Quantity	Unit	Unit Cost		Amount	
Mobilization	1	Lump Sum	\$	21,683	\$	21,683
Common Excavation	1000	CY	\$	12	\$	12,000
Concrete Ribbon Curb and Gutter	5350	LF	\$	18	\$	96,300
Bituminous Pavement	1860	Ton	\$	75	\$	139,500
Aggregate Base (CV) Class 5	470	CY	\$	30	\$	14,100
Select Granular Borrow Mod 10% (CV)	200	CY	\$	25	\$	5,000
Traffic Control	1	Lump Sum	\$	4,000	\$	4,000
Seed, Fertilize, and Mulch	1	Lump Sum	\$	8,000	\$	8,000
Erosion Control	1	Lump Sum	\$	6,000	\$	6,000
Signage	1	Lump Sum	\$	1,200	\$	1,200
Striping	1	Lump Sum	\$	3,000	\$	3,000
SUBTOTAL:					\$	310,783
15% Contingency:					\$	46,617
TOTAL:					\$	357,400

Note: Estimate assumes aggregate base, sand subbase, and drain tile have been previously installed in access roadway.